KEY: FINISH SCHEDULE

ACOUS.	ACOUSTIC	GYP.	GYPSUM
ACT	ACOUSTIC TILE	HM	HOLLOW METAL
ALUM.	ALUMINUM	N	NORTH
CMU	CONCRETE MASONRY UNIT	PLAST.	PLASTER
DW	DRYWALL	S	SOUTH
E	EAST	VCT	VINYL COMPOSITION TILE
EXT., EXIST.	EXISTING	W	WEST
GL	GLASS, GLAZING		

NOTE: PAINT ALL NEW AND EXISTING DRYWALL, PLASTER, BRICK, CMU, CONCRETE CEILINGS AND WALLS

NOTE: SEAL ALL CONCRETE FLOORS

ROOM FINISH SCHEDULE — GROUND FLOOR JAIL

NO.	NAME	FLOOR	BASE	WALLS	TYPE	CEILING MATL	CEILING TYPE	HGT	REMARKS
J001	STAIRWELL	VCT	VINYL	N,E,W - CMU S - EXIST. CMU	F8	EXPOSED STRUCTURE	F7	VARIES	ABRASIVE STRIPS. USE STRAIGHT BASE
J002	ELEVATOR EQUIPMENT	CONCRETE	NONE	N,E - CONCRETE S - CMU W - EXISTING	-- --	EXPOSED STRUCTURE	--	+/-9'	
J003	PUBLIC LOBBY	VCT	VINYL	N,S - CMU E,W - EXIST. CMU	F8	GYPSUM PLASTER	F7	8'-0"	
J004-1	HUBER VISITATION	VCT	NONE	CMU, HM & GLASS	F16 F11	GYPSUM PLASTER	F7	8'-0"	
J004-2	HUBER VISITATION	VCT	NONE	CMU, HM & GLASS	F16 F11	GYPSUM PLASTER	F7	8'-0"	
J004-3	HUBER VISITATION	VCT	NONE	CMU, HM & GLASS	F16 F11	CEMENT PLASTER	F7	8'-0"	
J004-4	HUBER VISITATION	VCT	NONE	CMU, HM & GLASS	F16 F11	CEMENT PLASTER	F7	8'-0"	
J005	CORRIDOR	VCT	VINYL	N,E,W - EXISTING S - CMU	F16 F11	CEMENT PLASTER	F7	8'-0"	
J006	JAIL VISITATION	VCT	NONE	CMU, HM & GLASS	F16 F11	CEMENT PLASTER	F7	8'-0"	
J007	VESTIBULE	VCT	VINYL	CMU, HM & GLASS	F16 F11	DETENTION PLASTER	F7	8'-0"	
J008	CORRIDOR	VCT	VINYL	N,S,W - CMU E - EXIST. CMU	F16	DETENTION PLASTER	F7	8'-0"	
J009	CORRIDOR	VCT	NONE	N,S,W - CMU E - EXIST. CMU	F16	DETENTION PLASTER	F7	8'-0"	
J009-1	CUSTODIAN	CONCRETE	NONE	N,E,W - EXISTING S - CMU	F8	EXPOSED STRUCTURE	--		
J009-2	INMATE VISITATION	VCT	NONE	CMU, HM & GLASS	F16 F11	DETENTION PLASTER	F7	8'-0"	
J010	JANITOR	CONCRETE	NONE	N,E,W - CMU S - EXIST. CMU	F8	EXPOSED STRUCTURE	--		
J011	HOLDING	CONCRETE	NONE	N,E,W - CMU S - EXIST. CMU	F16	DETENTION PLASTER	F12	8'-0"	
J012	HOLDING	CONCRETE	NONE	N,E,W - CMU S - EXISTING	F16	DETENTION PLASTER	F12	8'-0"	
J013	HOLDING	CONCRETE	NONE	N,E,W - CMU S - EXIST. CMU	F16	DETENTION PLASTER	F12	8'-0"	
J014	HOLDING	CONCRETE	NONE	N,E - CMU S,W - CMU, EXT. CMU	F16	DETENTION PLASTER	F12	8'-0"	
J015	GROUP HOLDING	CONCRETE	NONE	N,S,W - CMU E - EXIST. CMU	F16	DETENTION PLASTER	F12	8'-0"	
J016	BOOKING	VCT	VINYL	CMU	F8	CEMENT PLASTER	F7	8'-0"	
J017	SEARCH	VCT	VINYL	N,S,W - CMU E - EXIST. CMU	F8	CEMENT PLASTER	F7	8'-0"	
J018	LAVATORY	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	CEMENT PLASTER	F7	8'-0"	
J019	JAIL STORAGE	VCT	VINYL	N,W - CMU E,S - EXIST. CMU	F8	CEMENT PLASTER	F7	8'-0"	
J019-1	LOCKERS	CONCRETE	NONE	N, - EXIST. BRICK E,S,W - CMU	F8	CEMENT PLASTER	F7	8'-0"	
J020	CORRIDOR	VCT	VINYL	N,E,S - CMU W - EXIST. CMU	F8	CEMENT PLASTER	F7	8'-0"	
J021	WATER EQUIPMENT	CONCRETE	NONE	N - EXIST. CMU E,S,W - EXIST. CMU	--	EXPOSED STRUCTURE	--	8'-0"	
J022	EXAMINATION	VCT	VINYL	N,S - CMU E,W - EXISTING	F8	CEMENT PLASTER	F7	8'-0"	
J023	JAIL CONTROL	CARPET	VINYL	CMU HM & GLASS	F8 F11	CEMENT PLASTER	F7	8'-0"	
J024	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	CEMENT PLASTER	F7	8'-0"	
J025	MULTI-PURPOSE	CONCRETE	NONE	E,S,W - CMU N - HM & GLASS	F16 F11	EXPOSED STRUCTURE	F7	13'-0"	
J025-1	STORAGE	CONCRETE	NONE	N - CMU E,S,W - EXIST. CMU	F16	DETENTION PLASTER	F7	8'-0"	
J026	SALLYPORT	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	13'-0"	
J027	CORRIDOR	VCT	VINYL	CMU	F8	CEMENT PLASTER	F7	8'-0"	
J028	STAIRWELL	CONCRETE	EXISTING	EXISTING CMU	F8	EXISTING	F7	VARIES	
J029	MALE STAFF LOCKERS	CARPET	VINYL	N,E - CMU S,W - EXIST. CMU	F8	CEMENT PLASTER	F7	8'-0"	
J030	MALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	CMU	F16	CEMENT PLASTER	F7	8'-0"	
J0[illegible]	FEMALE STAFF LOCKERS	CARPET	VINYL	N,E,W - CMU S - EXIST. CMU	F8	CEMENT PLASTER	F7	8'-0"	
J032	FEMALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	CMU	F8	CEMENT PLASTER	F7	8'-0"	
J033	HOME DETENTION	VCT	VINYL	N,E,W - CMU S - EXIST. CMU	F8	CEMENT PLASTER	F7	8'-0"	
J034	CONFERENCE	VCT	VINYL	N,W - CMU E - DRYWALL S - EXIST. CMU	F8 F6 F8	~~DETENTION~~ PLASTER CEMENT	F7	8'-0"	
J035	LINEUP	VCT	VINYL	N,E,W - DRYWALL S - EXIST. CMU	F6 F8	CEMENT PLASTER	F7	8'-0"	
J036	CONFERENCE	VCT	VINYL	N,W - DRYWALL E,S - EXIST. CMU	F6 F8	CEMENT PLASTER	F7	8'-0"	
J037	CORRIDOR	VCT	VINYL	DRYWALL HM & GLASS	F6 F11	CEMENT PLASTER	F7	8'-0"	
J038	CONFERENCE	VCT	VINYL	N,E - EXIST. CMU S,W - DRYWALL	F8 F6	CEMENT PLASTER	F7	8'-0"	
J039	CONFERENCE	VCT	VINYL	N - EXIST. CMU E,S - DRYWALL W - CMU	F8 F6 F8	CEMENT PLASTER	F7	8'-0"	
J040	ASSISTANT JAIL ADMIN'TOR	CARPET	VINYL	N - EXIST. CMU S,E,W - CMU	F8	ACOUSTIC TILE	--	8'-0"	
J041	JAIL ADMINISTRATOR	CARPET	VINYL	N - EXIST. CMU S,E,W - CMU	F8	ACOUSTIC TILE	--	8'-0"	
J042	CORRIDOR	VCT	VINYL	N,E,S - EXIST. CMU W - CMU	F8	CEMENT PLASTER	F7	8'-0"	
J042-1	STORAGE	VCT	VINYL	N,S - EXIST. CMU E,W - CMU	F8	CEMENT PLASTER	F7	8'-0"	
J043	CORRIDOR	VCT	VINYL	N,E,S - CMU W - EXIST. CMU	F8	~~DETENTION PLASTER~~ CEMENT	F7	8'-0"	
J043-5	VISITATION	VCT	NONE	CMU HM & GLASS	F16 F11	~~DETENTION PLASTER~~ CEMENT	F7	8'-0"	
J043-6	VISITATION	VCT	NONE	CMU HM & GLASS	F16 F11	~~DETENTION PLASTER~~ CEMENT	F7	8'-0"	
J043-7	VISITATION	VCT	NONE	CMU HM & GLASS	F16 F11	~~DETENTION PLASTER~~ CEMENT	F7	8'-0"	
J043-8	VISITATION	VCT	NONE	CMU HM & GLASS	F16 F11	~~DETENTION PLASTER~~ CEMENT	F7	8'-0"	
J044	FEMALE HUBER INTAKE	VCT	VINYL	N - EXIST. CMU E,S,W - CMU	F8	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J045	FEMALE HUBER LOCKERS	VCT	VINYL	N,S,W - CMU E - EXIST. CMU	F8	~~DETENTION PLASTER~~ CEMENT	F7	8'-0"	
J046	CONFERENCE	VCT	VINYL	N,W - CMU E,S - EXIST. CMU	F8	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J047	TOILETS	CERAMIC TILE	GLAZED CMU	CMU	F16	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J048	FEMALE HUBER	CONCRETE	NONE	N,S,W - EXIST. CMU E - CMU	F8	DETENTION PLASTER	F2	8'-0"	
J049	SECURE CORRIDOR	VCT	VINYL	N,E,S - CMU W - EXIST. CMU	F8	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J050	MALE HUBER	CONCRETE	NONE	CMU	F8	EXPOSED STRUCTURE	F2	8'-0"	FACE EAST WALL W/ 4" CMU
J051	TOILETS	CERAMIC TILE	GLAZED CMU	CMU	F16	DETENTION PLASTER	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J052	HUBER	CONCRETE	NONE	CMU	F16	EXPOSED STRUCTURE	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J053	TOILETS	CERAMIC TILE	GLAZED CMU	CMU	F16	DETENTION PLASTER	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J054	HUBER	CONCRETE	NONE	CMU	F16	EXPOSED STRUCTURE	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J055	TOILETS	CERAMIC TILE	GLAZED CMU	CMU	F16	DETENTION PLASTER	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J056	HUBER	CONCRETE	NONE	CMU	F16	EXPOSED STRUCTURE	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J057	TOILETS	CERAMIC TILE	GLAZED CMU	CMU	F16	DETENTION PLASTER	F7	8'-0"	FACE EAST WALL W/ 4" CMU
J058	STORAGE	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	9'-0"	
J059	ELEVATOR EQUIPMENT	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	9'-0"	
J060	MECHANICAL	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	9'-0"	
J061	STAIRWELL	VCT	VINYL	CMU	F8	EXPOSED STRUCTURE	F7	VARIES	RUBBER TREAD ON RISERS
J062	STORAGE	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	9'-0"	
J063	CORRIDOR	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	9'-0"	
J065	CORRIDOR	VCT	VINYL	CMU	F8	GYPSUM PLASTER	F7	9'-0"	
J066	STAIRWELL	VCT	VINYL	CMU	F8	EXPOSED STRUCTURE	F7	VARIES	RUBBER TREAD ON RISERS
J066-1	CORRIDOR	VCT	VINYL	CMU	F8	GYPSUM PLASTER	F7	VARIES	
J067	MALE HUBER INTAKE	CONCRETE	NONE	N,S,W - CMU E - EXIST. CMU	F8	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J068	MALE HUBER INTAKE	CONCRETE	NONE	N,S,W - CMU E - CMU, EXIST. CMU	F8	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J069	HUBER INTAKE TOILETS	CERAMIC TILE	GLAZED CMU	CMU	F16	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J070	STORAGE	CONCRETE	NONE	N,S,W - CMU E - EXIST. CMU	F8	CONCRETE STRUCTURE	F7	9'-0"	
J071	JUVENILE MULTI-PURPOSE	CONCRETE EPOXY FINISH	NONE	N,S - CMU E,W - EXIST. CMU	F16 F8	DETENTION PLASTER	F7	8'-0"	
J072	JUVENILE CORRIDOR	VCT	VINYL	N,S - CMU E,W - CMU, EXT. CMU	F8	~~PLASTER~~ CEMENT	F7	8'-0"	
J073	JUVENILE VISITATION	VCT	NONE	N,E,S - CMU W - EXIST. CMU	F8	~~PLASTER~~ CEMENT	F7	8'-0"	
J073-1	JUVENILE VISITATION	VCT	NONE	CMU	F16	DETENTION PLASTER	F7	8'-0"	
J074	JUVENILE ENTRANCE	VCT	VINYL	CMU HM & GLASS	F8 F11	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J075	JUVENILE INTAKE	VCT	VINYL	CMU HM & GLASS	F8 F11	DETENTION ~~PLASTER~~ CEMENT	F7	8'-0"	
J076	JUVENILE DET. OFFICE	VCT	VINYL	N,S,W - CMU E - EXIST. CMU	F8	ACOUSTIC TILE	--	8'-0"	
J077	JUVENILE DAYROOM	CONCRETE	NONE	N - GRILLAGE E,W - EXISTING S - CMU	F9 F16 F16	DETENTION PLASTER	F7	8'-0"	
J078	JUVENILE CELL	CONCRETE	NONE	N,W - CMU S - GRILLAGE E - EXIST. CMU	F16 F9 F16	DETENTION PLASTER	F7	8'-0"	
J079	JUVENILE CELL	CONCRETE	NONE	N,E - CMU S - GRILLAGE W - EXIST. CMU	F16 F9 F16	DETENTION PLASTER	F7	8'-0"	
J080	JUVENILE DAYROOM	CONCRETE EPOXY FINISH	NONE	N,S - CMU E,W - CMU, EXT. CMU	F16	DETENTION PLASTER	F7	8'-0"	
J081	JUVENILE CELL	CONCRETE EPOXY FINISH	NONE	N,S,W - CMU E - EXIST. CMU W - GRILLAGE	F16 F6 F9	DETENTION PLASTER	F7	8'-0"	
J082	JUVENILE CELL	CONCRETE EPOXY FINISH	NONE	N,S - CMU E - EXIST. CMU W - GRILLAGE	F16 F9	DETENTION PLASTER	F7	8'-0"	
J083	JUVENILE DET. STORAGE	CONCRETE	NONE	N,E - EXISTING S,W - CMU	F8	EXPOSED STRUCTURE	F7	9'-0"	
J084	STAIRWELL	CONCRETE	NONE	N - CMU E,S,W - EXIST. CMU	F8		F7	VARIES	
J085	CORRIDOR	CONCRETE	NONE	CMU	F8	EXPOSED STRUCTURE	--	8'-0"	
J085-1	LIGHT WELL	CONCRETE	NONE	N,S,E - CONCRETE W - EXISTING	--	SKYLIGHT	--	8'-0"	
J086	VEHICLE SEARCH	CONCRETE	NONE	CMU	F8	EXPOSED STRUCTURE	--	9'-0"	
J087	EVIDENCE PROCESSING	CONCRETE	NONE	E,S - CMU N,W - EXIST. CMU	F8	EXPOSED STRUCTURE	--	9'-0"	
J088	SPECIAL EQUIPMENT	CONCRETE	NONE	N,S,W - CMU E - CONCRETE	--	EXPOSED STRUCTURE	--	9'-0"	
J089	WEAPONS	CONCRETE	NONE	N,S,W - CMU E - CONCRETE	--	EXPOSED STRUCTURE	--	9'-0"	
J090	SECURE EVIDENCE STORAGE	CONCRETE	NONE	N - CONCRETE E - CMU, CONCRETE S,W - CMU	F12 F8/12	EXPOSED STRUCTURE	F7	9'-0"	
J091	STORAGE	CONCRETE	NONE	N,E - CMU S,W - EXISTING	F16	CONCRETE	F7	8'-0"	
J092	DRYING	CONCRETE	NONE	N,E - EXISTING S,W - CMU	F8	CONCRETE	F7	8'-0"	
J093	INCINERATOR	CONCRETE	NONE	N,E - CMU S - CONCRETE W - EXIST. BRICK	-- --	EXPOSED STRUCTURE	--	9'-0"	
J094	VEHICLE MAINTENANCE	CONCRETE	NONE	N,E,W - CMU S - EXISTING	F8	CONCRETE	F7	9'-6" 20'-0"	VEHICLE HOIST
J095	GARAGE	CONCRETE	NONE	N,W - CONC., CMU E - CONCRETE S - EXIST. CONC., CMU	-- --	CONCRETE	--	9'-0"	
J096	CORRIDOR	VCT	VINYL	HM & GLASS CMU	F11 F16	CONCRETE DET. PLASTER	F7	12'-0"	
J097	EMERGENCY EXIT			CMU	F8	CONCRETE DET. PLASTER	F7	17'-0"	
J098	POD TOILETS	CERAMIC TILE	CERAMIC TILE	CMU CONCRETE	F16	CONCRETE	F7	8'-0"	
J099	POD CONTROL	CONCRETE	NONE	HM & GLASS CMU	F11 F8	ACOUSTIC TILE	F7	8'-0"	
J099-1	POD STORAGE	CONCRETE	NONE	CMU CONCRETE	F8	CONCRETE	F7	8'-0"	
J100	DAYROOM	CONCRETE	NONE	N,E,S - CMU W - GRILLAGE	F16 F9	CONCRETE	F7	17'-0"	
J100-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J101	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J102	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J103	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J104	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J105	DAYROOM	CONCRETE	NONE	N,S - WALLS CMU E - CMU, HM, GLASS W - GRILLAGE	F16 F11 F9	CONCRETE	F7	17'-0"	
J105-1	SHOWER	CERAMIC TILE	NONE	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J106	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J107	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J108	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J109	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J110	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J111	DAYROOM	CONCRETE	NONE	N - CMU, HM, GLASS E,W - CMU S - GRILLAGE	F11 F16 F9	CONCRETE	F7	17'-0"	
J111-1	SHOWER	CERAMIC TILE	NONE	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J112	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J113	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J114	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J115	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J116	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J117	DAYROOM	CONCRETE	NONE	N - CMU, HM, GLASS E,W - CMU S - GRILLAGE	F16,11 F16 F9	CONCRETE	F7	17'-0"	
J118	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J119	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J120	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J121	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J122	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J123	DAYROOM	CONCRETE	NONE	N,S - CMU E - GRILLAGE W - CMU, HM, GLASS	F16 F9 F16,F11	CONCRETE	F7	17'-0"	
J123-1	SHOWER	CERAMIC TILE	NONE	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J124	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J125	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J126	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J127	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J128	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J129	DAYROOM	CONCRETE	NONE	N,S - CMU E - GRILLAGE W - CMU, HM, GLASS	F16 F9 F16/F11	CONCRETE	F7	17'-0"	
J129-1	SHOWER	CERAMIC TILE	NONE	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J130	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J131	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J132	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J133	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J134	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J135	DAYROOM	CONCRETE	NONE	N - GRILLAGE E,W - CMU S - CMU, HM, GLASS	F9 F16 F16/F11	CONCRETE	F7	17'-0"	
J135-1	SHOWER	CERAMIC TILE	NONE	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J136	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J137	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J138	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J139	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J140	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J141	DAYROOM	CONCRETE	NONE	N - GRILLAGE E,W - CMU S - CMU, HM, GLASS	F9 F16 F16/F11	CONCRETE	F7	17'-0"	
J141-1	SHOWER	CERAMIC TILE	NONE	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J142	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J143	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J144	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	

ROOM FINISH SCHEDULE — FIRST FLOOR JAIL

NO.	NAME	FLOOR	BASE	WALLS	TYPE	CEILING MATL	CEILING TYPE	HGT	REMARKS
J200	CORRIDOR	CONCRETE	NONE	N,S - CMU E - RAILING W - GRILLAGE	F16 F10 F9	CONCRETE	F7	8'-0"	
J200-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J201	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J202	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J203	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J204	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J205	CORRIDOR	CONCRETE	NONE	N,S - CMU E - RAILING W - GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J205-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J206	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J207	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J208	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J209	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J210	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J211	CORRIDOR	CONCRETE	NONE	N - RAILING E,W - CMU S - GRILLAGE	F7 F16 F9	CONCRETE	F7	8'-0"	
J211-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J212	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J213	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J214	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J215	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J216	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J217	CORRIDOR	CONCRETE	NONE	N - RAILING E,W - CMU S - GRILLAGE	F F16 F9	CONCRETE	F7	8'-0"	
J217-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J218	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J219	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J220	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J221	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J222	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J223	CORRIDOR	CONCRETE	NONE	N,S - CMU E - GRILLAGE W - RAILING	F16 F9	CONCRETE	F7	8'-0"	
J223-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J224	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J225	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J226	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J227	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J228	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J229	CORRIDOR	CONCRETE	NONE	N,S - CMU E - GRILLAGE W - RAILING	F16 F9	CONCRETE	F7	8'-0"	
J229-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J230	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J231	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J232	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J233	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J234	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J235	CORRIDOR	CONCRETE	NONE	N - GRILLAGE E,W - CMU S - RAILING	F9 F16 F16	CONCRETE	F7	8'-0"	
J235-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	--	DETENTION PLASTER	F16	7'-0"	SEE DETAIL Q/A24
J236	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J237	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J238	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J239	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J240	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J241	CORRIDOR	CONCRETE	NONE	N - GRILLAGE E,W - CMU S - RAILING	F9 F16	CONCRETE	F7	8'-0"	
J241-1	SHOWER	CERAMIC TILE	GLAZED CMU	GLAZED CMU	F16	DETENTION PLASTER	F7	7'-0"	SEE DETAIL Q/A24
J242	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J243	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J244	CELL	CONCRETE	NONE	3 WALLS CMU 1 GRILLAGE	F16 F9	CONCRETE	F7	8'-0"	
J300	MECHANICAL CHASE	CONCRETE	NONE	CMU	F16 F9	EXPOSED STRUCTURE			

ROOM FINISH SCHEDULE — FIRST FLOOR SHERIFF'S DEPARTMENT

NO.	NAME	FLOOR	BASE	WALLS	TYPE	CEILING MATL	CEILING TYPE	HGT	REMARKS
S1000	VESTIBULE	SEAL'D CONC. - FLOOR MAT	VINYL	STONE	--	GYPSUM PLASTER	F7	10'-0"	RECESSED FLOOR MAT
S1001	PUBLIC LOBBY	CARPET	--	DW W/ VINYL WALL COVERING	--	GYP. PLAST. W/ ACOUS. PANEL	F7	8'-0"	
S1002	MALE PUBLIC TOILETS	CERAMIC TILE	CERAMIC TILE	N,E - DRYWALL S,W - CMU	F6 F8	GYPSUM PLASTER	F7	8'-0"	
S1003	FEMALE PUBLIC TOILETS	CERAMIC TILE	CERAMIC TILE	N,W - DRYWALL S,E - CMU	F6 F8	GYPSUM PLASTER	F7	8'-0"	
S1004	STAIRWELL	VCT	VINYL	CMU	F8	EXPOSED STRUCTURE	--	VARIES	FACE EXISTING S WALL WITH 4" CMU
S1005	VESTIBULE	VCT	NONE	N,W - EXIST. CMU E,S - CMU	F8	GYPSUM PLASTER	F7	8'-0"	
S1006	CORRIDOR	VCT	NONE	N,W - EXIST. CMU E,S,W - CMU	F8	GYPSUM PLASTER	F7	8'-0"	
S1007	LOADING DOCK	CONCRETE	NONE	CMU	F8	EXPOSED STRUCTURE	--	11'-0"	
S1008	SECURE VESTIBULE	QUARRY TILE	QUARRY TILE	CMU	F16	DETENTION PLASTER	F12	8'-0"	
S1009	DISHWASHING	QUARRY TILE	QUARRY TILE	CMU	F16	DETENTION PLASTER	F12	8'-0"	
S1010	KITCHEN	QUARRY TILE	QUARRY TILE	N,E,W - CMU S - EXIST. CMU	F16	CEMENT PLASTER	F12	9'-4"	
S1011	DRY STORAGE	QUARRY TILE	QUARRY TILE	N,S,W - CMU E - EXIST. CMU	F8	CEMENT PLASTER	F12	8'-0"	
S1012	OFFICE	QUARRY TILE	QUARRY TILE	N,W - CMU E,S - EXIST. CMU	F8	CEMENT PLASTER	F12	8'-0"	
S1013	COOLER	--	--	--	--	CEMENT PLASTER	--	8'-0"	PACKAGED UNIT. PLASTER TO 1'-0" BEYOND TOP OF UNIT
S1014	FREEZER	--	--	--	--	CEMENT PLASTER	--	8'-0"	PACKAGED UNIT. PLASTER TO 1'-0" BEYOND TOP OF UNIT
S1015	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F16	CEMENT PLASTER	F12	8'-0"	FACE SOUTH WALL WITH 4" CMU
S1015-1	LOCKER	QUARRY TILE	QUARRY TILE	CMU	F16	CEMENT PLASTER	F12	8'-0"	FACE SOUTH WALL WITH 4" CMU
S1016	JANITOR	CONCRETE	NONE	N,E,W - CMU S - EXIST. BRICK	F8	EXPOSED STRUCTURE	--	11'-0"	
S1017	LAUNDRY STORAGE	VCT	NONE	N,E - CMU S,W - EXIST. CMU	F8	CEMENT PLASTER	F12	8'-0"	
S1018	LAUNDRY	VCT	NONE	N,E,S - CMU W - EXIST. CMU	F8	CEMENT PLASTER	F12	8'-0"	
S1019	CORRIDOR	CARPET	VINYL	CMU DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
S1020	JANITOR	VCT	NONE	N,W - CMU S,E - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
S1021	CORRIDOR	CARPET	VINYL	N,W - CMU DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
S1022	FEMALE STAFF LOCKER	CARPET	VINYL	N,E,W - DRYWALL S - CMU	F6 F8	CEMENT PLASTER	F12	8'-0"	
S1023	FEMALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	--	CEMENT PLASTER	F12	8'-0"	
S1024	MALE STAFF LOCKER	CARPET	VINYL	N - CMU E,S,W - DRYWALL	F8 F6	CEMENT PLASTER	F12	8'-0"	
S1025	MALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	--	CEMENT PLASTER	F12	8'-0"	
S1026	TRAINING	CARPET	VINYL	N - FOLD. PARTIT'N S,E,W - DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1026-1	STORAGE	VCT	VINYL	N,E,W - DRYWALL S - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1026-2	GENERATOR	CONCRETE	NONE	N - EXIST. BRICK E,S,W - CMU	--	CONCRETE	--	9'-0"	LOUVER IN SOUTH WALL
S1026-3	COOLING TOWER	CONCRETE	NONE	N - EXIST. BRICK E,S,W - CMU	--	NONE	--	--	LOUVER IN SOUTH WALL
S1027	BRIEFING	CARPET	VINYL	N - DRYWALL	F8	ACOUSTIC TILE	--	8'-0"	MOVABLE PARTITION SOUTH
S1028	REPORTS	CARPET	VINYL	E,S - EXIST. CMU N,W - DRYWALL	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1029	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1030	SQUAD	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1031	LIEUTENANT	CARPET	VINYL	N,E,W - DRYWALL S - DW, EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1032	CLERICAL	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1033	OFFICE	CARPET	VINYL	N,E,S - DRYWALL S,W - DW, EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1034	STAIRWELL	EXISTING	NONE	EXISTING CMU	F8	EXISTING	--	VARIES	
S1035	MECHANICAL	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	19'-0"	
S1035-1	AIR HANDLING EQUIPMENT	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	19'-0"	
S1035-2	WIRING	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	19'-0"	
S1035-3	COMMUNICATIONS	CONCRETE	NONE	CMU	--	EXPOSED STRUCTURE	--	19'-0"	
S1036	OFFICE	CARPET	VINYL	N,E,S - DRYWALL W - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1037	PHOTO LAB	VCT	VINYL	N,E - DRYWALL S,W - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1038	STAFF LOUNGE	CARPET	VINYL	N,W - DW, EXIST. CMU S,E - DRYWALL	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1039	STORAGE	VCT	VINYL	DRYWALLL	F6	ACOUSTIC TILE	--	8'-0"	
S1040	SHIFT SARGENT	CARPET	VINYL	N,E,W - DRYWALL S - DW, EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1041	SHIFT SARGENT	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1042	SHIFT SARGENT	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1043	FEMALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	--	DRYWALL	F7	8'-0"	
S1044	MALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	--	DRYWALL	F7	8'-0"	
S1045	LAVATORY	CERAMIC TILE	CERAMIC TILE	DRYWALL	F6	DRYWALL	F7	8'-0"	RAISED FLOOR
S1046	DISPATCH LOUNGE	CARPET	VINYL	N,S,W - DRYWALL E - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	RAISED FLOOR
S1047	COMMUNICATIONS	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	ACCESSIBLE FLOOR
S1048	CORRIDOR	CARPET	VINYL	N,W - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1049	SECRETARY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1050	BOOKKEEPER	CARPET	VINYL	N,E,W - DRYWALL S - CMU	--	ACOUSTIC TILE	--	8'-0"	
S1051	SECRETARY	CARPET	VINYL	N,E,W - DRYWALL S - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1052	CHIEF DEPUTY	CARPET	VINYL	N,E,W - DRYWALL S - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1053	SHERIFF	CARPET	VINYL	DW W/ VINYL WALL COVERING	F6	ACOUSTIC TILE	--	8'-0"	
S1054	RECORD STORAGE	CONCRETE	VINYL	N - CMU E,S,W - DRYWALL	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1055	MEETING	CARPET	VINYL	N - CMU E,W,S - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	FOLDING PARTITION
S1056	DETECTIVE	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1057	DETECTIVE	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1058	SECRETARY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1059	METRO	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1060	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1060-1	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1061	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1062	STORAGE	CONCRETE	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1063	SARGENT	CARPET	VINYL	N,S,W - DRYWALL E - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1064	INTERVIEW	CARPET	VINYL	DRYWALL	F6	DRYWALL, ACOUS. TILE	F7	8'-0"	NORTH WALL GL-3; GLUE-ON ACT PANEL
S1065	DETECTIVE	CARPET	VINYL	N,S,W - DRYWALL E - EXISTING	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1066	INTERVIEW	CARPET	VINYL	N,E,S - DRYWALL W - EXIST. CMU	F6	DRYWALL, ACOUS. TILE	F7	8'-0"	SOUTH WALL GL-3; GLUE-ON ACT PANEL
S1067	DETECTIVE	CARPET	VINYL	N,S,W - DRYWALL E - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
S1068	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
S1069	DETECTIVE	CARPET	VINYL	N,E - EXIST. CMU S,W - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
S1070	INTERVIEW	CARPET	VINYL	N - EXIST. CMU E,S,W - DRYWALL	F8 F6	DRYWALL & ACOUS. TILE	F7 --	8'-0"	GLUE-ON ACOUSTIC TILE PANEL
S1071	STAIRWELL	CONCRETE	NONE	N - CMU E,S,W - EXIST. CMU	F6	EXPOSED STRUCTURE	F12	VARIES	ABRASIVE STRIPS
S1072	INTERVIEW	CARPET	VINYL	N,W - EXIST. CMU E,S - DRYWALL	F8 F6	DRYWALL & ACOUS. TILE	F7 --	8'-0"	GLUE-ON ACOUSTIC TILE PANEL
S1073	DETECTIVE	CARPET	VINYL	N,W - DRYWALL E,S - EXIST. CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	

ROOM FINISH SCHEDULE — FIRST FLOOR COURTHOUSE

NO.	NAME	FLOOR	BASE	WALLS	TYPE	CEILING MATL	CEILING TYPE	HGT	REMARKS
C1100	ENTRY STAIR	EXISTING TERRAZZO	EXISTING TERRAZZO	EXIST. CER. TILE & PLASTER	-- F6	EXISTING METAL PAN	--	VARIES	
C1101	CORRIDOR	EXISTING TERRAZZO	EXISTING TERRAZZO	EXISTING GRANITE & GLASS		EXISTING METAL PAN	--	7'-0"	SEE A & B/A4
C1102	FEMALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	N,S,W - CMU E - DRYWALL	F8 F6	DRYWALL	F7	8'-0"	
C1103	MALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	N,E,S - CMU W - DRYWALL	F8 F6	DRYWALL	F7	8'-0"	
C1104	EMPLOYEE LOUNGE	CARPET	VINYL	EXISTING CMU	F8	ACOUSTIC TILE	--	9'-2-3/8"	MATCH EXISTING CEILING HEIGHT
C1105	MECHANICAL	EXISTING	NONE	NO WORK REQ'D	--	EXISTING	--		
C1105-1	MECHANICAL	EXISTING	NONE	NO WORK REQ'D	--	EXISTING	--		
C1106	RECEPTION SECRETARY	CARPET	VINYL	N,E - CMU S,W - DRYWALL	F8 F6	ACOUSTIC TILE	--	9'-4"	
C1107	CLERICAL	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	9'-4"	
C1108	CLERK OF COURTS	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C1109	COURT ADMINISTRATOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C1110	VAULT	VCT	VINYL	CMU CMU	F8 F8	ACOUSTIC TILE	--	9'-4"	
C1111	SUPPLIES	VCT	VINYL	DRYWALL	F6	ACOUSTIC TILE		9'-4"	
C1112	LAW LIBRARY	CARPET	VINYL	N,S,W - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C1113	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C1114	RECEPTION SECRETARY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	9'-4"	SEE H/A28-B
C1115	JUDGE'S CHAMBERS	CARPET	WOOD	DRYWALL VINYL	F6	ACOUS. TILE & DRYWALL	-- F7	9'-4"	
C1116	JUDGE'S LAVATORY	CERAMIC TILE	CERAMIC TILE	DRYWALL	F6	DRYWALL	F7	8'-0"	
C1116-1	VESTIBULE	CARPET	WOOD	DRYWALL	F6	ACOUSTIC TILE		8'-0"	COAT RACK
C1117	CONFERENCE	CARPET	VINYL	DW W/ VINYL WALL COVERING	--	ACOUS. TILE & DRYWALL	-- F7	9'-4"	
C1118	CONFERENCE	CARPET	VINYL	DW W/ WINYL WALL COVERING	--	ACOUS. TILE & DRYWALL	-- F5	9'-4"	
C1119	JUDGE'S CHAMBERS	CARPET	WOOD	DRYWALL VINYL	F6	ACOUS. TILE & DRYWALL	-- F7	9'-4"	SEE CEILING & TRIM DETAILS
C1120	JUDGE'S LAVATORY	CERAMIC TILE	DRYWALL	DRYWALL	F6	DRYWALL	F7	8'-0"	
C1120-1	VESTIBULE	CARPET	WOOD	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	COAT RACK
C1121	ANTEROOM	CARPET	VINYL	N,E - DRYWALL S,W - REP. PLASTER	F6	ACOUSTIC TILE	--	9'-4"	CARPET STEPS
C1122	COURTROOM	CARPET	CUSTOM WOOD	N,S,W - VINYL WALL COV. & WOOD E - WOVEN FABRIC	-- F13	DRYWALL & HARDWOOD PANELS	-- F13	VARIES	SEE A28 AND A28-B
C1123	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C1124	WITNESS WAITING	CARPET	VINYL	N,E - CMU S - PLASTER W - DRYWALL	F8 F6 F6	ACOUSTIC TILE	--	8'-0"	
C1125	WITNESS WAITING	CARPET	VINYL	N - CMU E - DRYWALL S - PLASTER W - ALUM. & GLASS	F8	ACOUSTIC TILE	--	8'-0"	REPLACE EXISTING GLAZING WITH GL-12
C1126	JURY ASSEMBLY	CARPET	VINYL	EXIST. CMU	F8	ACOUSTIC TILE	--	9'-4"	
C1127	CORRIDOR	EXISTING TERRAZO	VINYL	DRYWALL	F6	ACOUSTIC TILE	--		CARPET RAMP
C1128	STAIRWELL	EXISTING	EXISTING	NO WORK REQ'D	F	ACOUSTIC TILE	--	VARIES	SEE DETAIL
C1129	PUBLIC LOBBY	CARPET & TERRAZZO	TERRAZZO	DRYWALL	F6	ACOUSTIC TILE	--	9'-4"	
C1129-1	STAIR / RAMP	CARPET & TERRAZZO	TERRAZZO	N,E,W - VINYL W.C. S - MARBLE	--	ACOUSTIC TILE	--	VARIES	
C1130	CUSTODIAN	VCT	VINYL	N,S - CMU E,W - EXIST. CMU	F8	DRYWALL	F7	8'-0"	
C1131	MALE PUBLIC TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	F6	DRYWALL	F7	8'-0"	
C1132	FEMALE PUBLIC TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	F6	DRYWALL	F7	8'-0"	
C1133	CONFERENCE	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C1134	CONFERENCE	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C1135	CONFERENCE	CARPET	VINYL	N,E,S - DRYWALL W - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C1136	HOLDING CELL	CONCRETE	NONE	CMU	F16	DETENTION PLASTER	F16	8'-0"	FACE EXISTING N WALL WITH 2" CMU
C1137	BAILIFF	VCT	VINYL	CMU	F8	PLASTER	F7	9'-4	FACE EXISTING N WALL WITH 2" CMU
C1138	CONFERENCE	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C1139	COURT STORAGE	VCT	VINYL	N - DRYWALL E,S,W - CMU	F6 F8	ACOUSTIC TILE	--	9'-4	
C1140	OFFICE	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C1141	STAIRWELL	VCT	VINYL	CMU	F8	ACOUSTIC TILE	--	VARIES	NON-SLIP NOSING
C1142	CORRIDOR	VCT	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C1143	CORRIDOR	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C1144	JURY	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-4	
C1145	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C1146	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C1147	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C1148	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C1149	JURY	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-4	
C1150	ANTEROOM	CARPET	VINYL	N,W,S - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	9'-4	
C1151	COURTROOM	CARPET	CUSTOM WOOD	WOVEN FABRIC, VINYL WALL COVERING, WOOD	-- F13	DRYWALL & HARDWOOD	F7 F13	VARIES	SEE A & B/A28
C1151-1	VESTIBULE	CARPET	VINYL	DRYWALL GLASS & ALUM.	F6	ACOUSTIC TILE	--	8'-0"	GL-1

ROOM FINISH SCHEDULE — SECOND FLOOR COURTHOUSE

NO.	NAME	FLOOR	BASE	WALLS	TYPE	CEILING MATL	CEILING TYPE	HGT	REMARKS
C2001	CORRIDOR	EXISTING TERRAZZO	EXISTING TERRAZZO	EXISTING GRANITE		EXISTING METAL PAN	--	7'-10"	SEE A & B A5
C2002	WITNESS WAITING	CARPET	VINYL	N,E - REP. PLASTER S,W - DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2003	WITNESS WAITING	CARPET	VINYL	N - REP. PLASTER E,S - DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2004	CORRIDOR	EXISTING TERRAZZO	EXISTING TERRAZZO	N,S - DRYWALL E,W - REP. PLAST.	F6	ACOUSTIC TILE	--	8'-0"	SEE A & B A5
C2005	MEETING	CARPET	VINYL	N,W,E - REP. PLAST. S - DRYWALL	F6	ACOUSTIC TILE	--	9'-4"	
C2006	CUSTODIAL	VCT	VINYL	N,S,E - DRYWALL W - REP. PLASTER	--	ACOUSTIC	--	8'-0"	
C2007	MALE PUBLIC TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	--	DRYWALL	F7	8'-0"	
C2008	FEMALE PUBLIC TOILETS	CERAMIC TILE	CERAMIC TILE	CERAMIC TILE	--	DRYWALL	F7	8'-0"	
C2009	STAIRWELL	EXISTING	EXISTING	EXIST. PLAST.	F6	ACOUSTIC TILE	--	VARIES	
C2010	STAIRWELL	VCT	VINYL	N,S - DRYWALL E - GLASS	F6	ACOUSTIC TILE	--	VARIES	
C2011	PUBLIC LOBBY	TERRAZZO	TERRAZZO	N,E - DW/VINYL S - STONE W - STONE/VINYL		DRYWALL ACT	F2	9'-4"	
C2012	CONFERENCE	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2013	CONFERENCE	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2014	COURTROOM	CARPET	CUSTOM WOOD	WOVEN FABRIC, VINYL WALL COVERING, WOOD	-- F13	DRYWALL & HARDWOOD	F7 F13	VARIES	SEE A, B & C/A28
C2014-1	VESTIBULE	CARPET	VINYL	FABRIC	--	ACOUSTIC TILE	--	8'-0"	GL-1
C2014-2	CONFERENCE	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C2015	ANTEROOM	CARPET	VINYL	N - CMU S,E,W - DRYWALL	F8 F6	ACOUSTIC TILE	--	9'-4"	
C2016	JURY	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-4"	
C2017	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C2018	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C2019	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C2020	LAVATORY	CERAMIC TILE	CERAMIC TILE	CMU	F8	DRYWALL	F7	8'-0"	
C2021	JURY	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-4"	
C2022	CORRIDOR	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C2023	LAW CLERK	CARPET	VINYL	N - DRYWALL E,S,W - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2024	HOLDING CELL	CONCRETE	NONE	CMU	F16	DETENTION PLASTER	F16	8'-0"	FACE NORTH WALL WITH 4" CMU
C2025	BAILIFF	VCT	VINYL	CMU	F8	PLASTER	F7	9'-4"	FACE NORTH WALL WITH 4" CMU
C2026	OFFICE	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C2027	CONFERENCE	CARPET	VINYL	N,E,S - DRYWALL W - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2028	COURTROOM	CARPET	CUSTOM WOOD	WOVEN FABRIC, VINYL WALL COVERING, WOOD	-- F13	DRYWALL & HARDWOOD	F7 F13	VARIES	SEE A & B/A28
C2029	ANTEROOM	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-4"	CARPET STEPS
C2030	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2031	SECRETARY /RECEPTION	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	9'-4"	
C2032	JUDGE'S CHAMBERS	CARPET	WOOD	DRYWALL VINYL	F6 --	ACOUS. TILE & DRYWALL	-- F7	9'-4"	SEE H/28-B
C2033	JUDGE'S LAVATORY	CERAMIC TILE	CERAMIC TILE	DRYWALL	F6	DRYWALL	F7	8'-0"	
C2033-1	VESTIBULE	CARPET	WOOD	DRYWALL	F6	ACOUSTIC TILE		8'-0"	COAT RACK
C2034	CONFERENCE	CARPET	WOOD	DW W/ VINYL WALL COVERING	F6	ACOUS. TILE & DRYWALL	-- F7	9'-4"	
C2035	CONFERENCE	CARPET	WOOD	DW W/ VINYL WALL COVERING	F6	ACOUS. TILE & DRYWALL	-- F7	9'-4"	
C2036	JUDGE'S CHAMBERS	CARPET	WOOD	DRYWALL VINYL	F6 --	ACOUS. TILE & DRYWALL	-- F7	9'-4"	
C2037	JUDGE'S LAVATORY	CERAMIC TILE	CERAMIC TILE	DRYWALL	F6	DRYWALL	F7	8'-0"	
C2037-1	VESTIBULE	CARPET	WOOD	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	COAT RACK
C2038	WITNESS COORDINATOR	CARPET	VINYL	N,W - CMU E,S - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
C2039	CONFERENCE	CARPET	VINYL	N,E - CMU S,W - DRYWALL	F8 F6	ACOUSTIC TILR	--	9'-4"	
C2040	CORRIDOR	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2041	DISTRICT ATTY. RECEPTION	CARPET	VINYL	N,E,W - DRYWALL S - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2042	ATTORNEY	CARPET	VINYL	N,W - DRYWALL E,S - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2043	CLERICAL	CARPET	VINYL	N,E,W - DRYWALL S,W - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2044	WORKSTATIONS	CARPET	VINYL	N,S,W - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2045	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2046	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2047	CONFERENCE	CARPET	VINYL	N,E,W - CMU S - DRYWALL	F8 F6	ACOUSTIC TILE	--	9'-4"	
C2048	SUPPLIES	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2049	PRIVATE WAITING	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2050	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2051	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2052	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2053	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2054	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2055	DISTRICT ATTORNEY	CARPET	VINYL	DRYWALL	F8	ACOUSTIC TILE	--	8'-0"	
C2056	OFFICE MANAGER	CARPET	VINYL	N,S - CMU E,W - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	48" X 48" WINDOW SOUTH WALL GL-1
C2057	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
C2058	ATTORNEY	CARPET	VINYL	DRYWALL	F6	ACOUSTIC TILE	--	8'-0"	
~~C2059~~	~~WORKSTATIONS~~	~~CARPET~~	~~VINYL~~	~~DRYWALL~~	~~F6~~	~~ACOUSTIC~~ TILE	~~--~~	~~9'-0"~~	
C2060	CHILD SUPPORT WAITING	CARPET	VINYL	N,S,W - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	9'-0"	EXISTING ENTRY SYSTEM
C2061	CHILD SUPPORT WORKSTATIONS	CARPET	VINYL	N - CMU E,S,W - DRYWALL	F6 F6	ACOUSTIC TILE	--	9'-0"	GL-12 EAST WALL
C2062	RECORDS	CARPET	VINYL	N,W - DRYWALL E,S - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2063	STAFF ATTORNEY	CARPET	VINYL	N,E - DRYWALL S,W - REP. PLASTER	F6	ACOUSTIC TILE	--	8'-0"	
C2064	SPECIALIST	CARPET	VINYL	N,W - CMU E,S - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
C2065	SPECIALIST	CARPET	VINYL	N,S,W - CMU E - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
C2066	SPECIALIST	CARPET	VINYL	N,S,W - CMU E - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
C2067	SPECIALIST	CARPET	VINYL	N,E - DRYWALL S,W - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2068	DIRECTOR	CARPET	VINYL	N,W - CMU E,S - DRYWALL	F8 F6	ACOUSTIC TILE	--	8'-0"	
C2069	MEETING	NO WORK REQ'D	NO WORK REQ'D	NO WORK REQ'D	--	EXISTING	--	-----	
C2070	LOUNGE	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-2.5"	
C2071	FEMALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	N,E,S - CMU W - DRYWALL	F8 F6	DRYWALL	F7	8'-0"	
C2072	MALE STAFF TOILETS	CERAMIC TILE	CERAMIC TILE	N,S,W - CMU E - DRYWALL	F8 F6	DRYWALL	F7	8'-0"	
C2073	REGISTER IN PROBATE	CARPET	VINYL	N,S - DRYWALL E,W - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	RENOVATE EXISTING RECEPT. COUNTER
C2074	REGISTRAR'S OFFICE	CARPET	VINYL	N,W - DRYWALL E,S - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2075	VAULT	VCT	VINYL	N,E - DRYWALL S,W - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2076	HEARING ROOM	CARPET	VINYL	N,S - DRYWALL E,W - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2077	FAMILY COURT COMMISSIONER	CARPET	VINYL	N,S - DRYWALL E,W - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2078	RECEPTION	CARPET	VINYL	N,E,S - DRYWALL W - CMU	F6 F8	ACOUSTIC TILE	--	9'-4"	
C2079	COUNSELOR	CARPET	VINYL	N,S,W - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2080	COUNSELOR	CARPET	VINYL	N,S,W - DRYWALL E - CMU	F6 F8	ACOUSTIC TILE	--	8'-0"	
C2081	CUSTODIAL	VCT	VINYL	CMU	F8	ACOUSTIC TILE	--	8'-0"	
C2082	GUARDIAN AD LITEM	CARPET	VINYL	CMU	F8	ACOUSTIC TILE	--	9'-4"	

DATE	REVISION

STRUCTURAL CONSULTANT

MECHANICAL CONSULTANT

ARCHITECT

KENTON PETERS + ASSOC., INC.
44 E. MIFFLIN
MADISON, WISCONSIN 53703
(608) 255-5656

JEFFERSON COUNTY
LAW ENFORCEMENT CENTER
JEFFERSON, WISCONSIN

ROOM FINISH SCHEDULE

6-11-90

A10

AS BUILT
DEC 6, 1994