1. Provide expansion joint covers at the following locations: Public corridor C1129 at entrance to elevator No. 2 floor (2hr. rated), joint at exterior face of existing wall; door and sidelite C1151-A 2hr. floor joint; door C1127-A 2hr. rated floor joint; door C1137-B 2hr. rated floor joint; 2hr. floor joint at base of stair between room C1121 and corridor C1143; floor joint at C122C; floor joint between corridor C1123 and C1113; floor joints at two openings between C1106 and C1107.

2. At North end of courthouse basement storage room J062; move door, stair and areaway 10'-0" to the West to avoid disturbing soil at existing footing.

3. Rebars indicated in wall types C, D, and E should be #4's @ 8"OC each way as per specifications.

4. At corridor elevations A and B glass type GL12 must match existing glass. Glass type GL12 not required to match existing elsewhere.

5. Wall type at North wall of C1107 clerical shown as H should be H10.

6. 4hr. wall between corridor 1142 and Room C1119, C1120 and between corridor C1113 and C1143 will require loose fill insulation from existing building to exterior wall of new construction.

7. 8" CMV wall 24'-0" long by height of room. Wall located approximately center of room in North/South direction per drawing S2. at storage room - basement plan North.

8. Room C2015 and C2029 at stairways add 30" long 1 1/2 round wall mounted pipe railing at right hand side of stairs.

S1054 and S1055: Revise the two 'R10' wall type designation to read 'K10'.

C1124: South wall is existing aluminum entry system rather than existing CMU indicated. Replace existing glass with new obscure glass type GL-12.

Door C1106-A; ~~Revise~~ Reuse existing door presently located in Aluminum Entry System between C1101 and C1106 bookkeepers/reception/secretary.

Add

9

10

11

A-4

7/19/90

AA67

MATCH LINE GROUND FLOOR

SEE SHEET A-2 LEFT SIDE

SEE G48 LEFT

G48

BASEMENT PLAN - NORTH

SEE WALL SECTIONS

MATCH LINE FIRST FLOOR

SEE AA67 THIS SHEET

SEE G200-D LEFT

SEE G188 LEFT

SEE G173 LEFT

SEE G67 LEFT

SEE G65 LEFT

HVAC RQ 289

ADD ONE ROW SEATING-ENLARGE SOFFIT RQ 314

ADDITIONAL OUTLET C1140 RQ 300

COURTHOUSE OFFICES FOR 4 DRYWALL PRE-CAST COLUMNS RQ 278

OPENING BETWEEN C1106 & C1107 3'-10 TO 7'-4 RQ 412

COFFEE NOOK RQ 301A

VISION LITE RQ 310

BUBBLER WITH SPOUT RQ 301B

FIBER FARMAD SCREEN RQ 307

VINYL BASE RQ 314-2

RAILING OUTSIDE DOOR C1142-A RQ 356

LARGER WINDOW ABOVE DOOR C1142-A RQ 310

4 HOUR WALL-LOOSE FILL INSULATION SEE #6 ABOVE

NEW 10'-0" WEST-SIDE NOTE 2 ABOVE

NEW STUD/GYP WALLS RQ 473

ELEVATION OF WEST CORRIDOR WALL

ELEVATION OF EAST CORRIDOR WALL

PLAN NORTH

LEGEND OF SYMBOLS

DOORS: "D" INDICATES DETENTION DOOR; 101/A — DOOR DESIGNATION, ROOM NUMBER, SECTION OF BUILDING (J-JAILS-SHERIFF, C-COURTHOUSE), DETAIL

ELEVATIONS DETAILS: K A26 — SHT.NO., DETAIL

WALL TYPES: 10 — WIDTH OF C.M.U.; — DENOTES THAT WALL EXTENDS TO STRUCTURE ABOVE; WALL TYPE

(F) FIRE EXTINGUISHER -WALL MOUNTED

F(C) FIRE EXTINGUISHER & CABINET

DIMENSION REFERENCE

C.M.U. VENEER (FINISH WALL) — BUILDING LINE

A — GROUTED

B — GROUTED & REINFORCED #5 @ 00 EACH WAY

C — 8",10" OR 12" NOM.C.M.U.'S AS INDICATED BY NO.

EXAMPLE 04 — INDICATES FULLY GROUTED 4" C.M.U. WALL

D — EXTERIOR CLADDING; 2" RIGID INSULATION; C.M.U. GROUTED & REINFORCED #5 AT 8'-0"O.C. EACH WAY

E — EXTERIOR EPOXY STUCCO SYSTEM; C.M.U. GROUTED & REINFORCED #5 AT 8'-0"O.C. EACH WAY

F — EXTERIOR EPOXY STUCCO; C.M.U.

G — EXTERIOR CLADDING; 2" RIGID INSULATION; C.M.U.

H — EXTERIOR CLADDING; 2" RIGID INSULATION; 5/8" GYP. BOARD; FURRING CHANNELS; C.M.U.

J — 5/8" GYP. BOARD; FURRING CHANNELS; C.M.U.; EXTERIOR EPOXY STUCCO

K — 5/8" GYP. BOARD; C.M.U.; FURRING CHANNELS

L — EXTERIOR METAL SIDING; FURRING CHANNELS; 1 1/2" RIGID INSULATION; C.M.U.

M — 5/8" GYP. BOARD; 3 1/2" STEEL STUDS

N — SOUND INSULATION; 3 1/2" STEEL STUDS; 5/8" GYP. BOARD; RESILIENT SOUND CLIPS

R — C.M.U.; FURRING CHANNELS; 5/8" GYP. BOARD

P — 1/2" GYP. BOARD; FURRING CHANNELS; LOOSE FILL INSULATION UL NO G419 80; C.M.U. UL 910-498 W/GYP BD. UL U901-4105 NO GYP BD

U — EXISTING WALL; FURRING CHANNELS; 5/8" GYP. BOARD

V — CONCRETE; EXTERIOR EPOXY STUCCO

T — EXISTING WALL; FURRING CHANNELS; 1/2" GYP. BOARD

NOTE:
WHERE EXISTING WALL, FLOORS, OR CEILINGS HAVE BEEN DISTURBED OR DAMAGED IN DEMOLITION ORBY THE INSTALLATION OF NEW WORK, PATCH THESE AREAS TO MATCH EXISTING FINISHES AND MATERIALS.

The judges have asked that some additional items be provided in each of the courtrooms.

1. Adhesive applied abrasive strips similar to those proposed for the terrazo be provided on the bench stair treads.
2. Install vinyl base on the interior of the jury box. RQ 444
3. Install a handrail at the witness box steps.

AS BUILT
DEC 6, 1994

STRUCTURAL CONSULTANT

MECHANICAL CONSULTANT

ARCHITECT
KENTON PETERS + ASSOC., INC.
44 E MIFFLIN
MADISON, WISCONSIN 53703
(608) 255-5656

JEFFERSON COUNTY
LAW ENFORCEMENT CENTER
JEFFERSON, WISCONSIN

FIRST FLOOR PLAN
COURTHOUSE
1/8"=1'-0"

5-11-90

A-1